

[illegible][illegible]

5775 Trapped particles  
A COMPARISON OF RADIO DATA AND MODEL CALCULATIONS  
OF JUPITER'S SYNCHROTRON RADIATION: II.  
E-W ASYMMETRY IN THE RADIATION BELTS AS A FUNCTION  
OF MAGNETIC LONGITUDE.  
I. de Pater (University of Minnesota, 1200 University  
Ave., Minneapolis, MN 55455) and J. H. Waite (University  
of Arizona, Tucson, Arizona 85721)  
We used a comparison of radio data with a  
model calculation of Jupiter's synchrotron radiation  
to show we have shown that the "hot region" in the  
planet's radiation belts cannot be explained by  
a simple model of a single source region. The  
left and right sides of the belt alone, which  
differ in size due to the higher order moments in  
the magnetic field, are not sufficient to explain  
the data. The model predicts that the radiation  
from the left and right sides of the belt should  
have an asymmetry in the ratio of flux at different  
magnetic longitudes  $\lambda = 240^\circ$  to  $360^\circ$  and the exis-  
tence of a dusk to dawn directed electric field  
over the entire magnetosphere. The model predicts  
this field results in a relatively larger amount  
of radiation from this side (at longitudes  $\lambda$   
between  $150^\circ$  and  $300^\circ$ ) or eastward in the  
region, the electric field, overabundance of elec-

**Cover.** Long-term velocities observed by fixed-point current meters at various locations and depths (given in meters on arrows) in the Mid-Atlantic Bight. Length of arrow gives magnitude of mean velocity (see scale on horizontal axis). (From *Scudlough et al.* [1978].)

Such simple theoretical models again suppose small displacements of the isopycnals from equilibrium and do not relate directly to situations involving, for example, the surface outcropping of the pycnocline. At present there is not much theoretical guidance to understanding the propagation of a

Current meter observations on the Oregon-Washington shelf in the early '70's provided direct and convincing evidence for the northward propagation of flow episodes that are unrelated to the wind (Kundu and Allen, 1976; Allen and






Fig. 2. Distribution of surface isotherms in Lake Ontario, observed by airborne radiation thermometry during IFYGL. Surface fronts separate the cold pool along the north shore from the rest of lake. The corresponding temperature distribution in a cross section of the coastal region was shown in Figure 7 of part 1 (Eos, January 13). Figure courtesy J. G. Irie, Atmospheric Environment Service, Toronto (from Csanady [1977]).

Kundu, 1978]. Figure 3 shows a comparison of winds and currents observed at the central transect of the 1973 CUE-2 (Coastal Upwelling Experiment) experiment. One flow episode centered at July 31 is clearly not wind driven. Figure 4 shows the northward propagation of the same event over a distance of about 80 km at a speed between 100 and 150 km/day. Along the 100-m isobath, the current fluctuations involved the entire water column and were strong enough to reverse the direction of the flow for about a 2-day period. During the same period, the temperature at 40-m depth was higher by about 0.5°C than before or after, showing that substantial isopycnal adjustment accompanied the episode. Although the precise flow structure of the event is not clear from the data, it seems reasonable to regard it as a hybrid Kelvin-topographic wave with an offshore trapping scale of the order of 20 km. A detailed analysis of the velocity structure supports this notion.

Faster waves (300–500 km/day) have also been inferred to travel along the same shelf at other times. The trapping width of these should be somewhat greater, and they may be closer to a homogeneous fluid or 'pure' topographic wave in modal structure. The occurrence of different wave modes and their relative rarity, given the dominance of direct quasi-local forcing by weather systems of large horizontal extent, explains why the statistical time series analysis of sea-level fluctuations, or of longshore velocities, tends to be confusing. The evidence for cyclonically propagating sea-level disturbances, warm and cold fronts, and current reversals is strongest and most detailed in the Great Lakes. The earliest clear demonstration of internal Kelvin wave propagation of a warm front around the southern end of Lake Michigan was given by Mortimer (1963). More detailed evidence on the propagation of internal Kelvin waves was obtained in Lake Ontario during International Field Year on the Great Lakes (IFYGL). At the end of July 1972, a series of eastward wind-stress impulses generated a system of coastal jets associated with appropriate upwells and downwells of the thermocline. By the end of the wind stress episode of 4 days duration, the thermocline tilt and current direction were reversed at some coastal transects. At the end of a further 4 days of calm weather, the reversal propagated virtually around the entire lake. The offshore trapping width was clearly seen in the experimental data to be of order 5 km, as suggested by a two-layer linear model, and the propagation speed was a corresponding 0.5 m/s. The modal structure of the wave was close to a hybrid topographic-internal Kelvin wave.

At a speed of 0.5 m/s, a wave travels around the perimeter of Lake Ontario in about 15 days. Blanton [1975] examined current meter spectra from Lake Ontario and found pronounced periodicities at 12–14 days. In October 1972, on the north shore of Lake Ontario, an upwelling event was also documented by using airborne radiation thermometry (see Figure 2 above). The sequence of surface isotherm maps for the period following the development of the upwelling clearly shows the slow propagation of the warm front, which marks the eastern end of the upwelling zone, toward the west and a similar movement of the cold front at its western end toward the east (Figure 5). The speed of propagation appeared to be somewhat less than internal Kelvin wave speed.

#### Flow Controlled by Bottom Friction

Over continental shelves of the Atlantic type, tidal currents are generally strong, with the result that turbulence level is high and the adjustment time to frictional equilibrium is short. Under such circumstances, circulation is dominated by steady flow episodes in which forcing by the wind is generally opposed by bottom stress, although not always or everywhere, the pattern of flow being also strongly dependent on topography.

The simple model of a developing longshore current (illustrated in Figure 2 of part 1 (Eos, January 13) did not take into account bottom friction. This is clearly unrealistic in very shallow water, where a substantial longshore transport could only develop if the velocity became very high. As the longshore velocity increases, so does bottom stress, until it balances the applied wind stress, or the longshore pressure gradient, if the latter is the driving force. The longshore current, and with it the transport, is thus limited in intensity by bottom friction. Important questions are, how large the limiting velocity and transport become, how long it takes for the flow to adjust to frictional equilibrium, and how the frictional adjustment time varies with depth.

Calculations based on a standard turbulent flow model, using a quadratic frictional drag formula, yield the estimate that for a 'typical' wind stress of 0.1 Pa (accompanying a 7 m/s wind), the flow adjusts to frictional equilibrium in about 3 h in a 10-m-deep water column. The adjustment time varies directly with depth and inversely with wind speed. In a hurricane blowing over shallow water, frictional equilibrium is very rapidly established. The limiting velocity of longshore flow at which the applied stress becomes balanced by bottom friction is about 0.2 m/s under average winds (0.1 Pa) but reaches 2 m/s in a hurricane.

Where tidal motions at moderate to high velocities occur, the wind-driven component of circulation may for many purposes be regarded as a perturbation on the tides. The period of the semidiurnal tide is the minimum period for which a 'circulation' component of the flow can be usefully defined or observed in such an environment. The value of the frictional adjustment time equals the semidiurnal period in water about 60 m deep under average conditions and is much shorter in strong winds. Thus even under average conditions, a typical Atlantic-type shelf responds in the frictional mode to forces affecting its circulation. This is even more obviously the case in stronger winds.

A realistic idealization of many continental shelves is to suppose isobaths straight and parallel to the coast. As in the simplest transient cases, the cross-isobath transport may be supposed to vanish within some range of the coast ('coastal constraint'). These simple idealizations imply for steady flow that the longshore slope of sea level remains constant with distance from shore. The magnitude of the longshore gradient is arbitrary and is the only free parameter available to represent the local effect of the basinwide (global) circulation on a limited coastal region or, in other words, to match the along-isobath flow that is supposed to occupy a given coastal region to the flow outside.

For a variable depth water column, the force balance between a longshore pressure gradient constant with distance from shore, wind stress, and bottom stress is analogous to what was discussed above for transient flow in a closed basin, with 'setup' opposing the wind stress. Along an open coast, however, the pressure gradient need not oppose the local wind. Where the pressure gradient supports the wind in generating longshore flow in a given direction, bottom stress must be strong enough to balance both. If the two are in opposition, the bottom stress must make up the difference. In shallow water, the pressure gradient force that is proportional to depth is small, and bottom stress must always oppose wind stress. Where the depth is large enough for the pressure gradient force to overwhelm the wind stress, bottom stress opposes the pressure gradient force. Thus if wind stress and longshore pressure gradient are in opposition, bottom stress vanishes along a critical isobath and changes sign on crossing this isobath. This is analogous to the change of acceleration in the transient current developing along the same isobath.

In relatively deep water (compared to the Ekman-layer depth), the interior of the water column is unaffected by friction. Here the longshore sea-level slope drives cross-isobath geostrophic flow. As the depth varies, so does the geostrophic cross-shore mass transport. For longshore wind stress constant with distance from shore, the divergence of the geostrophic cross-shore transport is absorbed by a bottom Ekman layer. This is possible because the pressure-gradient-driven flow becomes stronger in deeper water and generates higher bottom stress and a thicker bottom Ekman layer, which is able to conduct away the excess geostrophic cross-shore transport (Figure 6).




Fig. 3. Record of longshore wind, longshore current at five levels, and sea level at central transect of 1972 Coastal Upwelling Experiment (CUE) off Oregon. For most of the period, currents are directly wind driven, but an event centered on about July 30 is clearly unrelated to the local wind. (From Allen and Kundu [1978].)




Fig. 4. Longshore currents at 60-m depth at a series of moorings along the 100-m isobath off the Oregon coast during CUE 1972. Current at central transect ('Carnation') is repeated from Figure 3. End of July northing-related event (Poinsettia) to the north (Forget-Me-Not). (From Kundu and Allen [1978].)




Fig. 5. Distribution of surface isotherms in Lake Ontario 2 weeks after survey shown in Figure 2. Boundaries of cold pool along north shore are seen to have propagated cyclonically around a significant fraction of the lake perimeter. (From Csanady [1977].)




Fig. 6. Structure of flow driven by constant longshore pressure gradient ('slope') over continental shelf of variable depth. Distribution of longshore velocity ( $v(z)$ ) is similar to that in a laboratory channel, but it is accompanied by cross-shore flow  $u(z)$ , which is in geostrophic equilibrium with the longshore pressure gradient above a bottom frictional layer. The offshore Ekman transport in the latter balances onshore geostrophic flow (in the case illustrated) to satisfy the coastal constraint of zero cross-shore transport. Where the water is deeper, the same longshore pressure gradient drives more water shoreward, hence more must move seaward in the Ekman layer. This is possible only if the longshore bottom stress is greater, hence the water flows faster alongshore in deeper water.

#### Thermohaline Circulation

Although secondary in importance to the wind as a driving force, pressure differences within shallow seas also arise from horizontal density gradients caused by freshwater inflow or rapid heating and cooling of shallow water. These may be expected to generate their own 'thermohaline' circulation pattern, which combines with wind-driven circulation. The observed southwestward drift of shelf waters off the east coast of North America (north of Cape Hatteras) has repeatedly been attributed to freshwater inflow. In the Great Lakes, rapid early season heating of nearshore waters leads to the formation of a so-called 'thermal bar' which is associated with a slow cyclonic circulation.

Similar effects may be understood in the simplest terms by considering a two-dimensional infinite coast model in which nearshore freshening or heating occurs uniformly along the coast. Although freshwater sources are concentrated in rivers, river plumes mix with shelf water within a relatively narrow coastal boundary layer, so that it is not too unreasonable to idealize the freshwater inflow as uniformly distributed along the shoreline.

A uniform line source of freshwater that mixes with seawater because of storm- and tide-induced turbulence should give rise to constant density surfaces parallel to the coastline. The typical winter salinity distribution in the Mid-Atlantic Bight, for example, is of this kind. Except near the shelf edge, there is little density variation at any location between top and bottom of the water column, but the horizontal density gradients are significant in generating pressure gradients in a cross-shore direction. Longshore density gradients are small over most of the shelf and may be neglected in a first approximation. Similarly, in the Great Lakes, early season heating

leads to isothermal surfaces more or less parallel to the coast.

The pressure forces arising from such a density distribution accelerate the fluid in the first instance in an offshore direction at the surface, toward the shore near the bottom. If an imaginary vertical membrane that separates light nearshore fluid from heavier offshore fluid were withdrawn, cross-shore fluid motions would ensue until the Coriolis force deflected these into a longshore direction. The offshore-moving surface layers would develop cyclonic longshore velocity. The bottom layers, displaced shoreward, would acquire anticyclonic longshore motion. After adjustment to geostrophic equilibrium, the interface, originally at the imaginary membrane, would become tilted seaward at the surface, and sharp velocity differences would develop across the interface.

The density field associated with freshwater inflow or seasonal heating is relatively long-lived, and the transient behavior of a nearshore density front such as that just described should have little to do with the observed shape of such fronts. However, fronts of this type are unstable and subject to frequent breakdown, in the course of which they shed lenses of light fluid at the surface that move out into the heavy fluid and similar lenses of heavy fluid at the bottom that advance into light fluid along the bottom. Following breakdown of the front, geostrophic equilibrium is reestablished by inertia forces which restore a characteristic inclined frontal shape similar to what is generally observed at the edge of the shelf in the Mid-Atlantic Bight (Figure 7).

Why the constant property surfaces should be concentrated in a frontal zone at the edge of the shelf remains something of a puzzle at the present time. More nearly uniformly distributed density surfaces are sometimes also observed in the Mid-Atlantic Bight and other shallow seas. Whatever the details, cross-shore density gradients give rise to similarly directed pressure forces, and these are balanced by the Coriolis force of longshore flow. As may be expected, bottom friction reduces velocity near the bottom but leaves the cyclonically directed surface motion more nearly intact. Hence the general rule that thermohaline circulation that is due to freshwater inflow or nearshore heating is cyclonic. However, the intensity of such circulation is generally fairly low, surface thermohaline velocities being rarely as high as 0.1 m/s, except in frontal zones.




Fig. 7. Temperature and salinity distribution in a transect of the Mid-Atlantic Bight (Walsh et al., 1978). An S-shaped front at the edge of the shelf typically separates lighter, fresher shelf water from heavier, saltier water. Similar shapes may be calculated by allowing two initially separated fluid masses to adjust to geostrophic equilibrium. Light fluid on top moves parallel to the coast in a cyclonic direction (out of the picture).

#### Winter Circulation in the Mid-Atlantic Bight

As already remarked, the circulation of the east coast shelf of North America north of Cape Hatteras, specifically that of the Mid-Atlantic Bight, is characterized by a persistent southwestward drift. On time-averaging data over periods of 1 month or longer, a clear and consistent pattern of longshore and cross-shore velocities emerges that is reasonably regarded as a steady state flow field and is compared with the simple frictional equilibrium flow models just described.

The observed winter circulation of the Mid-Atlantic Bight has the following characteristics:

1. In the middle of the water column, there is longshore (long isobath, more accurately) flow toward the southwest at an intensity of 3–10 cm/s, increasing noticeably with increasing distance from shore.
2. In the middle of the water column the flow is onshore (cross-isobath) over most of the water column at an amplitude of 1–3 cm/s.
3. Surface waters move to the southwest at mean speeds of 10–30 cm/s and in an offshore direction at 3–10 cm/s.
4. Bottom waters diverge at about the 60-m isobath, moving in an onshore direction at 0–3 cm/s in shallower water, offshore at similar speeds in deeper water.

A figure from Beardsley et al. [1976] shows a summary of some of the observational evidence obtained from fixed point current meters, which mostly determine velocities above a bottom frictional layer and below the surface Ekman layer. (See cover figure.) Other evidence, obtained mostly by Lagrangian tracers, has been summarized by Bumpus [1973].

The observed facts may be explained as being caused by four mean circulation components that are due to north-easterly longshore wind stress, an opposing pressure gradient constant with distance from shore, offshore wind stress, and freshwater inflow, respectively. The interaction of longshore wind stress and opposing sea-level gradient is responsible for the increase of longshore velocity with distance from shore, according to the dynamical discussion above (see especially Figure 6). This also explains the divergence of the bottom boundary layer at a specific depth. The high offshore velocities at the surface result from the two wind-stress-related circulation components (caused by longshore and cross-shore wind, respectively) and from the thermohaline circulation.

#### Acknowledgments

This work has been supported by the Department of Energy under a contract entitled Coastal-Shelf Transport and Diffusion. A fuller, more quantitative version of essentially the same review will be published in 1981 in *Advances in Geophysics*.

#### References

- Allen, J. S., and P. K. Kundu, On the momentum, vorticity, and mass balance of the Oregon shelf, *J. Phys. Oceanogr.*, **8**, 13–27, 1978.
- Beardsley, R. C., W. C. Boicourt, and D. V. Hansen, Physical oceanography of the Middle Atlantic Bight, *Spec. Symp. Am. Soc. Limnol. Oceanogr.*, **2**, 20–34, 1976.
- Blanton, J. O., Nearshore lake currents measured during upwelling and downwelling of the thermocline in Lake Ontario, *J. Phys. Oceanogr.*, **5**, 111–124, 1975.
- Bumpus, D. F., A description of the circulation on the continental shelf of the east coast of the United States, in *Progress in Oceanography*, vol. 6, edited by B. A. Warren, pp. 111–159, Pergamon, New York, 1973.
- Csanady, G. T., Intermittent 'full' upwelling in Lake Ontario, *J. Geophys. Res.*, **82**, 397–419, 1977.
- Kundu, P. K., and J. S. Allen, Some three-dimensional characteristics of low-frequency current fluctuations near the Oregon coast, *J. Phys. Oceanogr.*, **8**, 181–199, 1978.
- Mortimer, C. H., Frontiers in physical limnology with particular reference to long waves in rotating basins, *Proc. Conf. Great Lakes Res.*, **6**, 6–42, 1983.
- Mysek, L. A., Topographically trapped waves, *Annu. Rev. Fluid Mech.*, **12**, 45–78, 1980.
- Reid, R. O., Effect of Coriolis force on edge waves, 1, Investigation of the normal modes, *J. Mar. Res.*, **16**, 109–144, 1958.
- Robinson, A. R., Continental shelf waves and the response of sea level to weather systems, *J. Geophys. Res.*, **69**, 367–388, 1964.
- Walsh, J. J., T. E. Whitledge, F. W. Barvenik, C. D. Wrick, S. O. Howe, W. E. Eastas, and J. T. Scott, Wind events and flood chain dynamics within the New York Bight, *Limnol. Oceanogr.*, **23**, 659–683, 1978.
- Yamagata, T., On cyclonic propagation of a warm front in a bay of a northern hemisphere, *Tellus*, **32**, 73–76, 1980.



## News

## Ozone Measurement Device

A new instrument mounted on an aircraft has been used by the EPA to measure ozone concentration and distribution in a column of atmosphere for the first time. The instrument is called Ultra Violet Differential Absorption LIDAR (UV-DIAL). Previous instruments could give such data on ozone only in the area immediately surrounding the aircraft. LIDAR, light intensity detection and ranging, is similar to radar but uses electromagnetic waves of much shorter wavelength.

The new instrument uses light of two different wavelengths. One of the wavelengths is absorbed by ozone, and the other is not. The difference between the two combined signals is analyzed by the UV-DIAL to determine concentration and distribution of ozone in a column beneath the aircraft.

Air sampling is done simultaneously between the aircraft and the ground at 50-ft intervals. Since the system can measure both total amount of ozone and its distribution in the column, three-dimensional mapping of ozone can be obtained quickly and cheaply by flying the airplane in a criss-cross pattern. This provides information needed for modeling ozone's generation, movement, and transformation.

Conventional LIDAR has been used for years to detect particulate matter in the atmosphere. In these LIDAR systems an extremely short pulse of light is fired from the airplane toward the ground. It travels downward through the air at the speed of light and is then scattered back to the system in proportion to the amount of fine particulates in the atmosphere.

Future plans for UV-DIAL include increasing its daylight sensitivity by using a more powerful laser and developing a similar instrument to measure sulfur dioxide. The range is now limited during certain daylight hours because solar radiation also scatters light off atmosphere particulates.—PMB

## Seabeam Echo Sounder

A Seabeam echo-sounder system, which produces a real-time contour map of the ocean floor from a moving ship, will be installed in the research vessel *Thomas Washington* during the fall of 1981. This will be the first such system installed in an American academic oceanographic ship. Acquisition and installation of the equipment was jointly supported by the Office of Naval Research (ONR) and by the Scripps Institution of Oceanography (SIO) with a grant from the Fleischman Foundation.

Use of the system is open to any investigator from any institution. A national scheduling advisory committee, appointed by ONR and SIO, held its first meeting at San Francisco, December 10, to establish the general areas of operation for the first 18 months of use. During this period the ship will work in the eastern north and equatorial Pacific, and the western North Atlantic, roughly between 15° S to 45° N, 30° W to 165° W. Proposals for work within this area should be sent to appropriate funding agencies (NSF, ONR, NOAA, DOE, et al.).

Information on costs, capabilities, and scheduling can be obtained from Ship Scheduling Office A-010, Scripps Institution of Oceanography, La Jolla, CA 92093 (phone 714/452-2840).

## NASA To Begin Construction of Aviation-Safety Test Facility

Construction of a \$7.5-million facility to research aviation safety will begin in April at NASA's Ames Research Center in Mountain View, California. Scheduled for completion in 1983, the facility will give scientists their first opportunity to identify and study psychological factors involved in the relationship between pilots, crew members, and modern aircraft.

The center will have two simulators. One will be a replica of a current transport airplane cockpit, complete with flight engineer's station, flight display, and control systems. The second will represent transport aircraft of the future. With advanced technology flight controls, displays, and other flight deck systems to accommodate a flight crew and observer, the advanced simulator will be designed to test human responses to the newest aviation technologies.

David Nagel, an aviation psychologist, and Rodger Hayes, project manager, are responsible for facility development. ☐

## Candidates for JGR-Blue Editor Sought

George L. Siscoe will complete his term as editor of the *Journal of Geophysical Research*—Blue at the end of 1981. A selection committee, chaired by Norman F. Ness, has been appointed to recommend candidates to the AGU president. Nominations for the editor for the space sciences section of JGR for the term 1982-1985 are now being accepted. Those who are interested in serving as editor, or who wish to suggest candidates, should send recommendations by April 15 directly to

American Geophysical Union  
2000 Florida Avenue, N.W.  
Washington, D.C. 20009  
Attention: JGR Search Committee.

## Observatory Ends Scientific Investigations

The Orbiting Astronomical Observatory (OAO-3), which was instrumental in the discovery of the first suspected black hole, wound up its scientific investigation at the end of 1980. Spacecraft science operations were terminated after 8½ years of operation. Named Copernicus, OAO-3 performed consistently beyond design specifications and 7½ years beyond project requirements. Its performance profile, according to the NASA-Goddard engineers and scientists, was "astounding."

While formal scientific investigations were ended December 31, a series of engineering tests are still being made until February 15. At that time, all contact with the spacecraft will end. Project engineers are uncertain whether Copernicus will orient itself permanently toward the sun, begin a permanent orbital tumbling action, or a variation of both.

Since its launch aboard an Atlas Centaur rocket August 21, 1972, from the Kennedy Space Center, Fla., the 2225-kg spacecraft has conducted its experiments from a 740-km-high orbit with a precision and clarity never before possible. Its supersensitive ultraviolet telescope, largest ever orbited, is capable of pointing accuracies equivalent to seeing a volleyball from a distance of 845 km. The 81-cm-diameter reflecting telescope provides data in the form of ultraviolet spectral readings otherwise invisible to ground-based observatories because of the obscuring effect of Earth's atmosphere. The instrument was built by Princeton University. Lyman Spitzer, Jr., is principal investigator.

University College, London, under sponsorship of the United Kingdom Science Research Council, provided the second instrument. It consists of three small telescopes and an associated counting device designed to study X-ray sources in space at various wavelengths. The experiment yielded important information on X-ray sources, such as candidate black holes and neutron stars, and was instrumental in the discovery of the suspected black hole, Cygnus X-1.

Copernicus also produced information on star temperatures, gravities, and chemical composition. Additionally, it studied the atmosphere of Earth, Mars, Jupiter, Saturn, Titan, and Io. During its operation, Copernicus was used by more than 180 investigators from the United States and 13 foreign countries to observe more than 450 unique objects.—PMB ☐

## Mt. St. Helens' Eruption Potential Lower

The potential for a large explosive eruption of Mount St. Helens fell below potential in December, according to measurements made in mid-January by scientists at the U.S. Geological Survey and the University of Washington. Increased seismic activity beneath the volcano at the end of December had prompted the issuance of an advisory on December 27. In addition, the following day a new lava dome was first sighted.

Prior to Christmas Day, two small earthquakes (less than 3 on the Richter scale) were recorded daily. Late Christmas Day, these events increased, reaching a maximum rate of four events per hour 2 days later.

A decline in seismic activity began on December 28; less than one earthquake was recorded per hour. This activity has continued to decrease to the background levels recorded

during the noneruptive periods of this past summer and fall, according to the USGS.

In addition to the decline in seismic activity, since January 4 the emission rates of sulfur dioxide and carbon dioxide from the volcano's crater have been two thirds of the emission rates of December. Latest measurements are comparable to the average rates in November. ☐

## Fulbright Awards Available

The Council for International Exchange of Scholars still is accepting applications for geology lecturers for 1981-1982. Nominations already made are being processed; most scholars receiving awards will be notified in February or March, according to the Council.

Available positions include one volcanic ash soils lecturer, Argentina; seismic analysis and antiseismic construction, Ecuador; geological engineering, Turkey; and petrology and/or optical mineralogy, Uganda. In addition, several positions are available for a lecturer in Liberia. For additional information, contact the Council, Suite 300, 11 Dupont Circle, Washington, D.C. 20036.

Announcement of opportunities available to American scholars for 1982-1983 will be published by April. ☐

## Senior Position in Earth Science

The Earth Sciences Division of the LAWRENCE BERKELEY LABORATORY has several comprehensive research programs involving the earth sciences. An opening exists for a person with an established national reputation in a scientific discipline in Earth Sciences, preferably geomorphology or hydrogeology, to assume a position of responsibility for the scientific leadership and direction of major research programs such as concerned with radioactive waste storage.

Duties will include taking the scientific initiative and direction and management of ongoing projects, including the nuclear waste isolation field involving more than 30 scientists and engineers at LBL and collaborative work with several academic and research organizations. Additionally, the position involves establishment of emerging programs, expansion of research facilities and pursuit of new areas of investigation.

The successful candidate should have extensive experience and proven capabilities in directing and achieving programmatic goals of complex research projects involving teams of senior scientists and engineers. A PhD in a field of the Earth Sciences is preferred with significant applicable experience. Salary: over \$50k.

Applications will be considered no later than April 1, 1981. Interested individuals should forward two resumes including salary history to: Employment Office, LAWRENCE BERKELEY LABORATORY, One Cyclotron Drive, Berkeley, CA 94720. An equal opportunity employer M/F.

LAWRENCE  
BERKELEY  
LABORATORY

## New Publications

**The Origin of the Southern Alps**  
R. I. Walcott and M. M. Cresswell (Eds.), *Bull. 18*, Royal Society of New Zealand, Wellington, 148 pp., 1979.

Reviewed by W. D. Means

Now that so many geologists have taken their plate tectonics pill and have recovered from the familiar seizure of enchantment or choking, a hopeful new era has begun in regional studies of young mountain belts. The central hope is that an accurate picture of orogenic movements for some Cenozoic belts can be reconstructed by fitting histories of local displacements consistent with on-land field studies to histories of the integrated displacements across entire belts inferred from marine magnetic anomalies and bathymetry. Therefore, special interest attaches to those relatively few places on earth where the marine features and the rocks on land are both well displayed and not too complicated. One such place is the South Island of New Zealand. It offers (1) a position astride the Indian-Pacific plate boundary, with continental crust both sides; (2) a relatively narrow zone (~200 km) through which most or maybe all of the interplate deformation is distributed; (3) a large component of recent shortening normal to the plate boundary, with associated large uplift of the glacier-hung Southern Alps and consequent good exposure; (4) a nearby seafloor triple junction around which a complete set of Cenozoic magnetic anomalies is preserved, such that long distance, multiple calculations are not needed for the plate tectonics; and, of course, (5) the famous Alpine Fault.

Bulletin 18 of the Royal Society of New Zealand, *The Origin of the Southern Alps*, takes stock of the Cenozoic tectonics of the South Island as understood late in 1978, following a meeting of the authors in May of that year convened by the New Zealand National Committee for Geodynamics. There are 17 short papers, all containing new data and ideas and nearly all by workers based in New Zealand. A wide range of land-based geological and geophysical investigations is described. A helpful editorial introduction mentions some other

recent and relevant work, to which I would add Molnar et al. [1978] (*Geophys. J.*, 40, 383-420), who give a plate tectonic interpretation of the seafloor data, and Walcott [1978] (*Geophys. J.*, 52, 137-164), who reviews late Cenozoic tectonics for the whole of New Zealand.

The papers discuss many questions of interest to workers outside New Zealand, among them: How are the interplate (horizontal) displacements distributed spatially, now and over the past few tens of millions of years? What is the partitioning of deformation between narrow zones of large displacement and velocity gradients (faults, shear zones, transposition zones, etc.) and broader areas of much smaller gradients? What is the history of uplift, its present rate, and its relationship to the horizontal movements? What is the three-dimensional configuration of the Alpine Fault and the reason for its apparent low seismicity? When did dextral movements start on the fault, and how are these related to the dextral "occlusion band" in the previously deformed pre-Cretaceous rocks? Some salient features have emerged, such as the fact that the Alpine Fault itself is currently taking up only about a third of the interplate velocity (Walcott) with the Southern Alps

somehow taking up the other two thirds. Uplift rates are currently high, of the order of a centimeter a year along the crest of the range (Wellman). The locus of most rapid uplift lies offset some kilometers to the east of the surface trace of the Alpine Fault (Wellman, J. Adams, C. J. D. Adams). A total Cenozoic uplift of 5-10 km has occurred since late Miocene time (C. J. D. Adams). The mountains are hot, with temperatures of several hundred degrees predicted within 2 km of the surface (Allis, Henley, and Carman). Despite progress on many fronts, the authors would probably agree that *Bulletin 18* only scratches the surface of what can eventually be learned about the answers to the basic questions. Some of the present interpretations differ from one paper to the next, like Wellman's idea that the Alpine Fault flattens eastward and becomes horizontal at 30 km versus Woodward's suggestion that the fault extends in some form down to 50 km without great change in a moderately steep, easterly dip. I found the whole volume absorbing. I liked Walcott's brave attempt to draw shear strain-rate profiles across the Southern Alps, based on meager retriangulation data and the plate velocity constraint, and Norris's even more daring effort to

unstrain a large part of the South Island by using a grid of old fault traces as markers. Both made their assumptions clear. I liked J. Adams' measurement, using millimetric fault steps on the glacially polished surface of a schist outcrop, of very recent vertical motion near the Alpine Fault. I savored Wellman's conception that a listric east-dipping Alpine Fault, up which the Southern Alps are pushed, is paired with a deep west-dipping "anti-fault" that carries the lower lithosphere back down beneath the mountains. *Bulletin 18* is full of innovations. Even the publisher has a go. There are tables of data interspersed in one of the reference lists, a case of figure captions transposed between two papers, and one entirely blank page in the middle of a paper. These novelties and the glaring misprints in many papers make one wonder whether the authors ever saw proofs. Never mind. *Bulletin 18* makes enjoyable reading in more ways than one. I recommend it to all tectonicians.

W. D. Means is with the Department of Geological Sciences, State University of New York at Albany, Albany, New York.

## Classified

EOS offers classified space for Positions Available, Positions Wanted, and Services, Supplies, Courses, and Announcements. There are no discounts or commissions on classified ads. Any type that is not publisher's choice is charged for at display rates. EOS is published weekly on Tuesday. Ads must be received in writing on Monday 1 week prior to the date of the issue required.

Positions Wanted: Rates per line: 1-5 times—\$1.00, 6-11 times—\$0.75, 12-26 times—\$0.55.

Positions Available: Rates per line: 1-5 times—\$2.00, 6-11 times—\$1.80, 12-26 times—\$1.40.

Services, Supplies, Courses, and Announcements: Rates per line: 1-5 times—\$2.50, 6-11 times—\$1.95, 12-26 times—\$1.75.

## POSITIONS AVAILABLE

**Geologist/University of Washington.** The University of Washington seeks applications for a tenure track position with the individual to be appointed as assistant professor jointly in the Department of Atmospheric Sciences and Geophysics programs. Principal research interest of candidates should be directed toward geophysical or climate related study of snow or ice. Candidates specializing in physical processes in snow are of particular, but not exclusive, interest. All applicants should be committed to graduate level teaching, research advising, and innovative research emphasizing advanced experimental methods and rigorous physical analysis. Duties will include teaching one or two undergraduate courses per year in atmospheric sciences. The appointment starts in September 1981. A Ph.D. is required. For additional information call C. F. Raymond (206) 543-4914. Interested persons may send a resume and four letters of recommendation to Professor R. T. Merrill, Geophysics Program AK-60, University of Washington, Seattle, WA 98195. Deadline for application is 31 March 1981. An equal opportunity/affirmative action employer.

**Assistant Professor: Planetary Sciences.** The Astronomy Department at Cornell University invites applications for a faculty position in the general area of planetary sciences. The position is a tenure track assistant professorship to begin September 1981 or 1982. The department has a strong program of solar system studies, emphasizing telescopic, radar, and spacecraft observations of planetary surfaces and atmospheres, with associated theoretical investigations in the areas of atmospheric dynamics, planetary interiors, and celestial mechanics, as well as supporting laboratory programs.

Outstanding research ability is the most essential qualification. Teaching ability, including the supervision of graduate research students, is also an important requirement.

Candidates should send a resume with bibliography and a summary of research interests and experience to:

Professor Yervant Terzian  
Chairman, Department of Astronomy  
Space Sciences Building  
Cornell University  
Ithaca, NY 14853

Candidates should also arrange for three letters of recommendation to be sent to the above address. All application materials must be received by April 30, 1981.

Cornell University is an equal opportunity/affirmative action employer.

**Faculty Appointment/Colorado State University.** The Department of Earth Resources, Colorado State University, invites applications for a tenure track appointment with emphasis on active research experience in remote sensing, and an interest in teaching graduate and undergraduate students beginning September 1981. The candidate is expected to have a Ph.D. degree in geology, watershed sciences or in a related field and is expected to develop and maintain a vigorous research program with special emphasis on the application of state-of-the-art remote sensing techniques to the investigation of natural resources phenomena. The candidate is expected to teach undergraduate and graduate courses in the application of remote sensing to natural resources.

Rank and salary are open and dependent on experience and qualifications of the applicant.

Applicants are invited to submit curriculum vitae, three letters of reference and a letter describing research and teaching interests to Dr. H. S. Boyne, Department of Earth Resources, Colorado State University, Fort Collins, Colorado 80523 (303) 491-6288.

Deadline for receipt of applications is April 15, 1981.

CSU is an EOE/AA. E.O. Office: 314 Student Serv. Bldg.

**Environmental Resources Engineering/Humboldt State University.** One or two positions are available for tenure track faculty positions are anticipated for fall 1981. The first position requires expertise in geotechnical engineering with specialization in soil mechanics. Capabilities in sediment transport and/or structural mechanics are also desirable. The second position requires expertise in water quality, water resources, energy resources or related areas. Special consideration will be given to applicants with field experience and the ability to participate actively in existing teaching and research programs. A Ph.D. in civil engineering or closely allied field is required. Forward resume plus the names of three references by March 1, 1981, to G. M. Anderson, Chairman, Department of Environmental Resources Engineering, Humboldt State University, Arcata, CA 95521.

The University is an equal opportunity employer.

**Meteorologist.** Sigma Data Computing Corp.'s Division of Information and Scientific Applications invites applications from meteorologists qualified to participate in an environmental modeling/chemical state assessment team effort.

The applicant will evaluate atmospheric models and their data requirements to form a comprehensive multimedia modeling library system for assessment of local chemical. The applicant will also provide recommendations for modification of existing model algorithms and R&D for anticipated continuing model development.

An M.S. degree or equivalent experience is a minimum requirement. Programming experience in FORTRAN and use or development of air quality models is desirable but not essential.

Salary is commensurate with qualifications. Please submit resume and references to:

Fogor Long  
Sigma Data Computing Corp.  
2021 K Street, N.W.  
Suite 207  
Washington, D.C. 20006

## ASSISTANT DIRECTOR

### FOR INSTITUTE OF GEOPHYSICS AND PLANETARY PHYSICS AT LOS ALAMOS NATIONAL LABORATORY, UNIVERSITY OF CALIFORNIA

Distinguished scientist with demonstrated administrative record sought to head a new branch of the University of California's Institute of Geophysics and Planetary Physics (IGPP) that has recently been established at the Los Alamos National Laboratory, Los Alamos, New Mexico.

This fourth branch of IGPP needs a leader to build a program suitable for Los Alamos and the remainder of the University of California. The successful applicant will serve both as Assistant Director of the Los Alamos National Laboratory reporting to the Director and as an Assistant Director of IGPP. The Assistant Director will be responsible for the coordination with the remainder of the University of California through the Director of Systemwide IGPP, O. L. Anderson.

**REQUIREMENTS:** Extensive research experience in a field related to the geosciences, an extensive publication record, proven managerial ability within a scientific organization, excellent communication skills, a Ph.D. or equivalent experience in Earth Sciences, Physics, or Chemistry.

Respond to Dr. Donald M. Kerr, Director, Los Alamos National Laboratory, DIV 81-AF, Los Alamos, New Mexico, 87545. Applications must be received by March 31, 1981.

# Los Alamos

## Los Alamos National Laboratory

### Los Alamos, New Mexico 87545

An Affirmative Action/Equal Opportunity Employer. Women, Minorities, the Handicapped, and Veterans are Urged to Apply. U.S. Citizenship Required.

**Assistant Professor/Civil Engineering.** The University of Mississippi invites applications for a position of assistant professor in civil engineering beginning in August, 1981. The Department has an engineering science-oriented ABET accredited undergraduate program and ongoing graduate programs in the areas of soil mechanics, fluid mechanics, hydrology, and sedimentation engineering. Applicants should have a Ph.D. in civil engineering or some closely related field with a specialty in one or more of the fields mentioned above. Duties include teaching and supervising students. Salary commensurate with experience. Apply by April 15, 1981, or until position is filled; to Dr. Samuel L. DeLesseau, Department of Civil Engineering, University of Mississippi, University, MS 38677.

Equal opportunity employer.

**Von Braun Post-Doctoral Fellowship in Space Physics/University of Alabama.** Appointment effective September 1981 in a tenure track assistant professorship with reduced teaching load during the first two years. Research specialty in astrophysics, planetary science or solar terrestrial physics. Research support available from NASA and Redstone Arsenal. Salary commensurate with experience. The applicant is invited to send resume, research plans and names of four references. Apply to: Von Braun Fellowship Committee, Office of Academic Affairs, University of Alabama in Huntsville, AL 35896.

Equal opportunity in education and employment.

**Faculty Position Openings at M.I.T.** The Ralph M. Parson Laboratory of the Water Resources and Environmental Engineering Division, Department of Civil Engineering, at the Massachusetts Institute of Technology, offers a wide range of educational and research programs in:

Hydrodynamics and Coastal Engineering  
Hydrology and Water Resource Systems  
Aquatic Sciences, Water Quality Control  
and Environmental Engineering

This program in the broad field of engineering in the water environment currently has 14 faculty and 60 full-time graduate students. During the next year we are seeking to add one or two new faculty appointments at the assistant professor level to increase the robustness of our various activities. We seek bright, self-starting individuals capable of defining and developing their special interest within the supportive structure of a state-of-the-art interdisciplinary group. Thus, rather than narrow disciplinary outlines, we instead ask for statements of interest from qualified individuals working within the above spectrum. If you are interested in making further inquiries about a faculty position, please send an outline of your particular interest area, goals and objectives, along with a resume to:

Professor Donald R. F. Harleman  
Director  
Ralph M. Parsons Laboratory  
Room 48-311  
Massachusetts Institute of Technology  
Cambridge, MA 02139

M.I.T. is an equal opportunity employer.

**Postdoctoral Fellow/Department of Terrestrial Magnetism, Carnegie Institution of Washington.** Endowed postdoctoral fellowships in private institutions, emphasizing maximum freedom of research in areas of geophysics, isotopes and trace element geochemistry, mass spectrometry, planetary geology, and star and planet formation. Renewable for second year. Women and minority candidates encouraged. Completed applications due March 1, 1981. For information write Fellowship Committee, Dept. of Terrestrial Magnetism, Carnegie Institution of Washington, 524 15th Street Branch Road, N.W., Washington, D.C. 20018.



# NRL SUPERINTENDENT, Space Science Division NAVAL RESEARCH LABORATORY Washington, D.C.

Salary \$52,247 to \$57,673 (current pay limitation is presently \$50,112.50 per annum)

**DUTIES:** As head of a division of 130 scientific, technical and support personnel, directs a broad program of basic and applied research in space science. Areas of particular interest are upper atmospheric physics, ionospheric physics, magnetospheric physics, solar physics, x-ray astronomy, UV astronomy, gamma-ray astronomy, and radio and infrared astronomy. The division is involved in extensive joint programs with the National Aeronautics and Space Administration (NASA). The division also includes the E.O. Hulbert Center for Space Research which provides a program for graduates and postgraduate students and visiting faculty members to cooperate with NRL in space research.

**TO APPLY:** Interested applicants should contact James Horn of the personnel office at (202) 767-3030 (call collect) to obtain application forms and information on procedures for applying.

All applications must be received by 28 February, 1981.

NAVAL RESEARCH LABORATORY  
Civilian Personnel Office  
Code: 40-019-11 EOS  
4555 Overlook Avenue, S.W.  
Washington, D.C. 20375  
An Equal Opportunity Employer

**Structural Geologist.** The Department of Geosciences of Purdue University invites application for a tenure track faculty position in structural geology. Starting in August 1981 Rank and salary will be commensurate with qualifications. A Ph.D. is required. The individual will be expected to teach undergraduate and graduate courses in structural geology and tectonics, participate in summer field courses, and pursue an active research program. Preference will be given to a candidate with an applied field orientation and a strong background in the quantitative analysis of field data. The department has active programs in petrology, geophysics, and engineering geology and has a close working relationship with the geotechnical group in civil engineering and the Laboratory for Applications of Remote Sensing. Closing date for application is April 1, 1981. Applicants should send a resume, the names, addresses, and telephone numbers of three referees, and a brief statement of research interests to R. H. McCarter, Department of Geosciences, Purdue University, West Lafayette, IN 47907. Purdue University is an equal opportunity affirmative action employer.

**Stable Isotope Geochemistry/University of Saskatchewan.** The Department of Geological Sciences has a vacant tenure track position at the assistant professor level for a stable isotope geochemist. Applicants should hold (or be about to receive) the Ph.D. degree, be qualified to instruct undergraduates in general geology and undergraduate and postgraduate students in geochemistry and petrology. Be prepared to pursue a vigorous research program, and to assume the duties of a geochronologist. Research laboratory with a McJannet 902 Deuterium Correcting Mass Spectrometer. Letters of application, with curriculum vitae including the names of at least three referees, should be sent to W. G. E. Cadée, Head, Department of Geological Sciences, University of Saskatchewan, Saskatoon, Canada, S7N 0W0.

**Geophysicist.** The Geology Department at the University of Southwestern Louisiana in Lafayette, Louisiana invites applications for an anticipated research teaching opening in geophysics. Responsibilities will include one-half time in a seismic investigation of geopressured-geothermal reservoirs of South Louisiana and one-half time teaching geophysics and supervising graduate students. The successful applicant will be familiar with exploration seismic data acquisition, processing, and interpretation. The Ph.D. or Masters with experience, is required. Salary range is \$23,000 to \$35,000 per 12 month. The position is expected to be filled in the Spring of 1981 or as soon as possible thereafter. To apply please direct a resume, letters of recommendation, and any other pertinent materials to Dr. Gary L. Kinsland, Geology Department, University of Southwestern Louisiana, Lafayette, LA 70504.

**Stable Isotope Geochemist/University of Minnesota.** The Department of Geology and Geophysics seeks an applicant for a tenure track assistant professor position for the academic year 1981 in the general field of stable isotope geochemistry. Applicants must have a Ph.D. degree by the time of appointment. The successful candidate will be expected to establish a laboratory facility, to supervise independent research, and to teach existing faculty graduate and undergraduate courses in isotope geochemistry. Research programs in the stable isotope geochemistry of igneous, sedimentary, and metamorphic rocks, and the relationships between these rocks and the atmosphere and hydrosphere are of particular interest. The successful candidate will be expected to participate in ongoing programs in geochemistry, geophysics, petrology, paleogeography, sedimentology, hydrology, mineralogy, petrology, geophysics, etc. The previously advertised search has been extended until March 15, 1981. Send curriculum vitae, relevant reports, research interests, and letters from three referees to: E. C. Abelson, Department of Geology and Geophysics, University of Minnesota, 310 Pillsbury Drive S.E., Minneapolis, MN 55455. The University of Minnesota is an equal opportunity employer and specifically invites and encourages applications from women and minorities.

**Acadia University.** The Department of Geology, Acadia University, is seeking a head, beginning July 1, 1981. Preference will be given to applicants with experience and research interests in petroleum geology and related fields and/or energy resources. Rank and salary will be commensurate with qualifications. The successful candidate will assume leadership of an established, vigorous and growing department with five faculty members, and over 100 B.Sc. and M.Sc. candidates. Responsibilities include teaching at undergraduate and graduate levels, and academic planning and development in the specialty area. A letter of application together with a curriculum vitae and names of three referees should be sent by March 15, 1981 to Dr. Ernest E. Zinck, Dean of Science, Acadia University, Wolfville, N.S., B0P 1X0.

**Faculty Positions/University of New Orleans.** The Physics Department of the University of New Orleans invites applications for two tenure track positions expected to be available August 1981. Rank and salary are to be commensurate with experience and training. The department has a policy of encouraging research activities in applied areas which are of mutual interest to the faculty and the local technical community. Candidates with background in computational physics, acoustics, and geophysics are especially encouraged to apply. Current research activities within the department include experimental studies in the areas of: solid state physics, cryogenic geophysics, hydrodynamics, and computational physics. Applicants should send a resume to Edward L. Beeson, Chairman, Physics Department, University of New Orleans, LA 70122. The University is an equal opportunity affirmative action employer.

**Faculty Positions in Geology/University of Alabama.** The Department of Earth Science is seeking applicants for a tenure track position at the assistant professor level. The Ph.D. degree is required. The selected person will teach one or more basic courses in earth science, will supervise senior more elective courses in that person's specialty, and will develop a research program. The Department of Earth Science consists of four full-time faculty and graduate assistants include a senior each year. Equipment and facilities include a geochemical and sedimentation laboratory, rock preparation equipment, student and research petrographic equipment, Elson stereographic equipment, transit and slide, drafting facilities, and computer equipment. Salary is competitive and commensurate with experience and education. Applicants should send a resume, three letters of reference, and a brief discussion of research interests to Michael J. Nelson, Earth Science Department, University of Alabama in Birmingham, Birmingham, Ala. 35294, prior to May 1, 1981. The position will be available September, 1981. The University of Alabama in Birmingham is an equal opportunity/affirmative action employer.

**Drexel University/Atmospheric Scientist.** Three tenure track faculty positions are anticipated starting fall 1981. Applications are solicited from Ph.D.s with independent research experience in one or more of the following areas of atmospheric science: gas-surface meteorology, atmospheric optics, planetary meteorology, or theoretical work with emphasis in mesoscale atmospheric chemistry modeling and atmospheric chemistry modeling. Rank and salary commensurate with experience. Send resume and references to Dr. William W. Eide, Head, Department of Physics and Atmospheric Science, Drexel University, Philadelphia, PA 19104. An equal opportunity/affirmative action employer.

**Postdoctoral Research Associate/Mineralogy.** Applications are invited for research in high-resolution analytical transmission electron microscopy of minerals and their analogues. Experience in crystallography, materials science, or electron microscopy is desirable. Send resume (including transcripts), statement of research interests, and names of three references to P. B. Bown, Department of Geology, Arizona State University, Tempe, AZ 85281. Arizona State University is an EEO/AA employer.

**Sedimentary or Low Temperature Geochemist.** This is an assistant professor, tenure track position, although exceptional candidates of higher rank will be considered. We are looking for a geochemist to complement our strong programs in sedimentology, hydrogeology, organic geochemistry, and basin analysis. The teaching load is three courses per year: one beginning level geology course, an upper level geochemistry course, and a graduate course of higher choosing. Introductory geology and summer field camp are also taught on a long-term rotating basis. A well-equipped laboratory and computer facilities are available. The potential exists both for outside funding and for cooperative research. The successful candidate will be expected to conduct an active research program leading to publication. Applicants should submit a letter of application, resume, a copy of each transcript, and have three supporting letters sent to: Chairman, Department of Geology, University of Missouri, Columbia, Missouri 65211. The University of Missouri is an equal employment opportunity employer.

**Postdoctoral Research Associate.** Oceanography Department of the Naval Postgraduate School seeks recent graduate to study the hydrodynamics, through numerical ocean modeling of the physical oceanographic processes active in the vicinity of the Arctic ice edge off Alaska. Problem areas include the effects of the complex bathymetry on the circulation and frontal formation, the dynamics associated with interweaving of water masses at the ice edge, and the mechanisms involved in ice retreat. Research will be performed in the context of an observational program which has acquired data and developed insights over the course of several years. Position is available March 1981 and is renewable annually. Salary depends upon qualifications. Send resume and names and addresses of three references to Faculty Search Committee, Dept. of Oceanography, Naval Postgraduate School, Monterey, CA 93940. Equal opportunity/affirmative action employer.

**Program Manager/Meteorology.** Oceanographic Services, Inc., is seeking qualified applicants for the position of program manager for meteorological studies. Applicants should have an M.S. or Ph.D. in meteorology or atmospheric science, plus experience in the field. A broad general knowledge of air pollution, and an understanding of the air pollution regulatory environment, is helpful. Interested persons should send resume, references, and salary history to R. C. Banks, Oceanographic Services, Inc., 26 Castillon Drive, Gaithersburg, MD 20878.

**Personnel Administrator.** Aret Associates, P.O. Box 350, Encino, CA 91316. An equal opportunity employer M/F.

**Remote Sensing/Ocean Engineering or Oceanography Faculty Position.** Applications are solicited for two permanent nine-month positions involving both research and graduate and undergraduate teaching. Ability to initiate and conduct research is desirable. Send resume, brief statement of research areas, and the names of three references to F. W. Morris, Search Committee, Department of Oceanography and Ocean Engineering, Melbourne, FL 32801. Equal Opportunity Employer.

**Research and Data Systems, Inc./Scientific Programmers and Programmer Analysts.** Immediate openings for persons with B.S. degree in math and at least two years experience with FORTRAN or PL/I on IBM systems. Work involves data processing and analysis from satellite based remote sensing systems. Experience with time sharing systems preferred. Also have openings for staff scientists with strong programming background. Send resume in confidence to Research and Data Systems, Inc., 8420 Annapolis Road, Lanham, MD 20801. Telephone: (301) 468-0001.

**Assistant Research Professor.** A non-tenure track position in geological sciences at the University of Washington for a person qualified to run an active research program in <sup>14</sup>C dating. Experience with thermal diffusion <sup>14</sup>C enrichment technique with knowledge of the application of Van de Graaf accelerator to ultra-high sensitivity <sup>14</sup>C mass spectrometry essential. Salary: \$17,000-\$21,000. Curriculum vitae, including two references to be sent by February 15 to M. Shuler, Search Committee, Department of Geology, University of Washington, Seattle, WA 98195. The University of Washington is an Affirmative Action/Equal Opportunity Employer.

**Oceanographic Mooring Technician.** The Marine Science Program at North Carolina State University (Raleigh) is expanding its oceanographic technical services group and is currently seeking a technician familiar with the design and deployment of deep-sea current meter mooring arrays, as well as standard shipboard oceanographic sampling techniques. Qualifications include a degree in science or engineering with some electronics background and two years field experience or an equivalent combination of education and experience. Salary commensurate with education and experience. Send resume and names of three references to Personnel Services, North Carolina State University, P.O. Box 5087, Raleigh, NC 27650. An equal opportunity employer.

**Geochemistry/Brittle Deformation, University of New Brunswick.** The Department of Geology has a tenure track position available from July 1, 1981 at assistant professor or higher level. The successful applicant will be expected to teach both undergraduate and graduate as well as carrying out research and supervising graduate students. Applications will be accepted in the following fields: geochemistry of ore bodies, exploration, environmental or soil geochemistry, brittle deformation, or petrology or earth engineering. Applicants should have a Ph.D. and preferably post doctoral experience. Applications including a curriculum vitae and names of three references should be sent to P. F. Williams, Chairman, Department of Geology, University of New Brunswick, Fredericton, N.B. E3B 6A5. N.B. is an equal opportunity employer.

**Virginia Polytechnic Institute and State University.** Igneous Petrology and Geochemistry Research Associate. Origin and tectonic significance of granitic rocks. Project involves petrography, analytic chemistry, mineral chemistry, isotopic studies, and field mapping. Send resumes to: D. R. Wones, Chairman, Department of Geological Sciences, Virginia Poly. Inst. and St. Univ., Blacksburg, VA 24061. The University is an equal opportunity/affirmative action employer.

**Hydrologist.** Sigma Data Computing Corp.'s Division of Information and Scientific Applications invites applications from hydrologists qualified to participate in an environmental modeling/chemical fate assessment team effort. The applicant will evaluate terrestrial and groundwater models and their data requirements to form a comprehensive multimedia modeling library system for assessment of toxic chemicals. The applicant will also provide recommendations for modification of existing model algorithms and R&D for anticipated continuing model development. An M.S. degree or equivalent experience is a minimum requirement. Programming experience in FORTRAN and use or development of water quality models is desirable but not essential. Salary is commensurate with qualifications. Please submit resume and references to: Roger Long, Sigma Data Computing Corp., 2021 K Street, NW, Suite 207, Washington, D.C. 20006.

**Physical Oceanographer/Geophysical Fluid Dynamist.** Aret Associates, a growing research firm, located in Southern California, engaged in theoretical and empirical physical oceanography, is offering permanent, full-time positions. Candidates require Ph.D. (or equivalent experience) in physical oceanography or geophysical fluid dynamics. Salaries are competitive and negotiable, based on qualifications. Aret offers a fringe benefit package superior to quality. Qualified candidates should send resume, salary history, and list of professional references to: Personnel Administrator, Aret Associates, P.O. Box 350, Encino, CA 91316. An equal opportunity employer M/F.

**Research Assistant/Utah State University.** Existing opportunities at the frontier of knowledge exist for graduate and undergraduate research assistants in the Department of Electrical Engineering at Utah State University, USU, located at the base of the Wasatch Mountains, is engaged in ground-breaking investigations in many critical fields. Get involved in environmental sensing, digital electronics, microprocessor applications, electro-optics, in science and engineering applications and atmospheric physics with state-of-the-art instrumentation on the ground, in rockets, or aboard the space shuttle. For details on these and other projects, contact Doran J. Baker, Head, Department of Electrical Engineering, UMC 416, Utah State University, Logan, UT 84302 (telephone: 801/750-5840). USU provides opportunities based only upon performance.

**Staff Scientist/Ocean Margin Drilling Program.** Joint Oceanographic Institutions, Inc. (JOI, Inc.) has immediate openings for two staff scientists to fill the positions of: -Downhole Measurements Coordinator in the Ocean Margin Drilling (OMD) Science Programs Office. Individuals filling each of these positions will report to the OMD Chief Scientist. They will be required to provide staff support to advisory committees in their area of concern, and will be responsible for implementing programs recommended by the OMD Science Advisory Committee, including oversight of the performance of individuals or groups in an appropriate area of earth science and appropriate experience. The OMDP is funded for FY '81. Initial appointment will be for a period of two years with the second year contingent upon the availability of funds. The positions may be filled on a rotating basis. Salary will be competitive. Send resume, statement of interest, and the names of three references to Thomas A. Davies, Chief Scientist, Ocean Margin Drilling Program, Joint Oceanographic Institutions, Inc., 2000 Virginia Ave., NW, Suite 612, Washington, DC 20037. The deadline for applications is February 20, 1981, or as soon thereafter as suitable candidates are found.

**NBF.** The National Science Foundation, Division of Ocean Sciences, is seeking qualified applicants for the position of program director in the Physical Oceanography Program. The position is exempt from the competitive civil service. This appointment is for a period of 1-2 years. The program provides support for scientists primarily from academic institutions to pursue fundamental research in physical oceanography. The selected candidate will carry out program planning and budgeting, proposal evaluation, administration of research grants, and liaison with other federal agencies. Applicants should have a Ph.D. in physical oceanography, a related physical science, or the equivalent, plus at least 3 years of specialized experience in physical oceanography. Field experience in an academic institutional program is highly desirable. Salary range is from \$37,871 to \$50,112.50, depending on qualifications and experience. Those interested in being considered for the position should send letters of interest and SF-171 or current resumes to the National Science Foundation, Personnel Administration, 1800 G St., N.W., Rm. 812, Washington, DC 20505. Attn: E. Paul Brodie. For further information call (202) 357-7841. NBF is an equal opportunity employer.

**Sediment Transport/Geological Oceanography.** A tenure track position is available in the Department of Marine, Earth and Atmospheric Sciences at the level of assistant or associate professor. Applicants should have a thorough understanding of sediment transport, and a general background in geological oceanography. A Ph.D. is required. The candidate will be expected to strengthen the graduate teaching and research programs. The applicant's research interests can be theoretical, experimental, or observational, but must involve quantitative examination of marine sediment transport. Applicants should forward a resume, including a list of courses taken/taught, and the names of at least three references to Dr. Charles A. Nittrouer, Chairman, Search Committee, P.O. Box 5088, NC State University, Raleigh, NC, 27650. Application materials should be sent by March 31, 1981. North Carolina State University is an equal opportunity/affirmative action employer.

**Faculty Position UCLA.** Tenure faculty position—associate or full professor—in planetary atmospheric sciences. It is expected that an opening will soon become available for a senior scientist who has demonstrated exceptional accomplishment in the area of atmospheric sciences. Preference will be given to an individual whose interests are in atmospheric chemistry with particular stress on the composition and evolution of planetary atmospheres. The successful individual will have a joint appointment in the Department of Atmospheric Sciences and the Institute of Geophysics and Planetary Physics. Please send resumes to: Leon Knopoff, Institute of Geophysics, UCLA, Los Angeles, Calif. 90024. UCLA is an equal opportunity/affirmative action employer.

**Sedimentologist.** The State University of New York at Binghamton has a vacancy for a sedimentologist at the assistant professor level. Candidates with research interest in exploration geophysics or earthquake seismology and a solid theoretical background are encouraged to apply. A Ph.D. with 0 to 5 years of teaching, research, and/or industrial experience is appropriate for the position. Salary is negotiable and competitive with academic institutions. Position is available in fall 1981. Please send resume and evidence of teaching and research proficiency, by March 31, 1981, and arrange for early submission of four letters of recommendation to Dr. Arthur G. Sylvester, Chairman, Department of Geological Sciences, University of California, Santa Barbara, CA 93106. (805) 961-3155. The University of California is an affirmative action/equal opportunity employer.

## Meetings

### Radio Glaciology Workshop

A Radio Glaciology Workshop, organized by the World Data Center-A for Glaciology (Snow and Ice), will be held September 4-5 in Columbus, Ohio, in conjunction with the Third International Symposium on Antarctic Glaciology. The workshop will focus on data acquisition and processing and data archiving and distribution. A working document will be produced that summarizes the key scientific, technical, and data management needs that relate to radio glaciology data acquisition, processing, archiving, and distribution.

For more information and for registration materials, contact Peter K. MacKinnon, WDC-A for Glaciology, CIREB, Box 449, University of Colorado, Boulder, Colorado 80309 (telephone: 303/492-5171). \$

### Antarctic Earth Sciences Symposium

The Fourth International Symposium on Antarctic Earth Sciences will be held at the University of Adelaide, Australia, August 15-21, 1982. The symposium tentatively will include technical sessions on the Archean and Proterozoic record, southern ocean

marine geology, solid earth geophysics, Cenozoic climate, plate tectonics, glacial geology, and Tertiary to recent volcanism. Two excursions are planned.

The symposium is sponsored by the Australian Academy of Science, the Australian Academy of Technological Sciences, the International Union of Geological Sciences, the Scientific Committee on Antarctic Research, the Geological Society of Australia, Inc., and the University of Adelaide.

For additional information, contact J. B. Jago, South Australian Institute of Technology, P.O. Box 1, Ingle Farm, South Australia, Australia 5098. \$

(cont. on page 48)

## SOCIETY FOR INDUSTRIAL AND APPLIED MATHEMATICS CONFERENCE ON MATHEMATICAL AND COMPUTATIONAL METHODS IN THE EXPLORATION AND EXTRACTION OF DEEP MINERAL RESOURCES NOVEMBER 16-19, 1981 TUCSON, ARIZONA CALL FOR PAPERS AND GENERAL ANNOUNCEMENT

SIAM is conducting a special conference on mathematical and computational methods in mineral exploration and extraction of Tucson, Arizona on November 16-19, 1981. The conference will feature nearly twenty invited speakers on electromagnetic methods, potential field methods, and seismic methods in exploration; conventional and novel methods for extraction; and ocean mining. The speakers will focus especially on the problems relating to deep deposits, especially of non-fuel minerals.

### SYMPOSIUM AND INVITED SPEAKERS

#### EXPLORATION

**Electromagnetic Methods:** Peter Annon, Barringer Research Ltd., on processing and interpretation of COIRAN and INPUT data. Gerald W. Hohmann, College of Mines and Mineral Industries, on modeling and processing deep EM and IP data. K. G. McCracken, Minerals Research Laboratory, on borehole logging and borehole geophysics. M. N. Nabighian, Newmont Exploration Ltd., on deep TEM exploration—mathematical and computational methods. **Potential Field Methods:** Alberto R. Calderon, University of Chicago, title to be announced. Thomas R. La Fehr, Exploration Data Consultants, Inc., on interactive computer graphics for integrated geophysics and geology. Richard B. McCammon, U.S. Geological Survey, on geological factor models for evaluating undiscovered mineral resources. **Seismic Methods:** Norman Bleislin, University of Denver, title to be announced.

#### Conference Program Committee

Robert Burridge, (committee chairman), Courant Institute of Mathematical Sciences, New York University; Victor Barallon, University of Chicago; Norman Bleislin, University of Denver; Neville G. W. Cook, University of California; Norman E. Goldstein, University of California; Milton Wadsworth, University of Utah; Stanley H. Ward, University of Utah; William D. Woodbury, U.S. Department of the Interior.

#### REGISTRATION

Advance registration material will be available in October, 1981. For additional information, contact Mr. H. B. Hair, SIAM, 417 South 17th Street, Philadelphia, PA 19103. Telephone: (215) 564-2929.

Following tradition, SIAM is scheduling contributed papers sessions and poster presentations, in addition to the invited speakers. CONTRIBUTED PAPERS AND POSTER PRESENTATIONS WILL BE CONSIDERED ONLY IF THEY ARE CONSISTENT WITH THE THEME OF THE CONFERENCE. Contributors should indicate to which of the specific conference areas their papers relate.

Abstracts should be submitted on forms provided by SIAM by June 15, 1981. See instructions below.

**EXTRACTION**  
**Conventional Methods:** Michel David, Ecole Polytechnique and Mineral Exploration Research Institute, on a review of mathematical problems in ore reserve estimation.  
**Novel Methods:** Robert W. Barlett, Anaconda Copper Company, on physical-chemical phenomena to be modeled in leaching metals from ore heaps. James G. Gilmer, Rockefeller University, title to be announced. Chester McKee, University of Wyoming, on mathematical problems relevant to in situ recovery of minerals.  
**OCEAN MINING**  
Phillip Grole, Science Applications, Inc., on characterization and analysis of operational performance—DOM systems. Jim Kosal, International Submarine Technology Ltd., on remote ocean bottom characterization techniques applicable to resource assessment.

### Contributed Papers and Poster Presentations How to contribute

Contributions—only in areas consistent with the theme of the conference—should be submitted on a SIAM standard abstract form. Abstract forms may be obtained from SIAM, 117 South 17th Street, Suite 1405, Philadelphia, PA 19103. Telephone: (215) 564-2929. **Deadline for abstracts:** SIAM must receive contributed abstracts—200 words or less—by June 15, 1981.